



# TOWN OF HALIFAX COMMONWEALTH OF MASSACHUSETTS

## Board of Health

499 Plymouth Street, Halifax, MA 02338  
Telephone (781)293-6768 \* Fax (781)293-1738

### Soil Evaluators and Engineers

1. If the design plan requires removal and replacement of unsuitable soils, the depth of the removal and replacement, to suitable pervious material, will be noted on the plan.
2. Please add the depths in inches next to the elevations in the soil test data chart and the chart of flow line grades.
3. Charcoal filters must be installed on all SAS vents.
4. Zabel filters (or equal) must be installed in outlets of all systems.
5. Electric junction boxes must be installed outside of the wet well of the pump chamber.
6. Monolithic tanks will be required if tank sits in ground water or if tank is within 200 feet of surface water supply.
7. There will be a 24 hour test for tight tanks.
8. All proposed and As-Built septic plans are required to show contours of said site and at least 25' beyond in all directions.
9. All purpose and As-Built plans shall indicate wells within 100 feet of system.
10. If retaining walls are used in the system, there shall be a certification by a structural engineer that the wall was constructed as originally designed and approved.
11. An approved copy of the proposed plan and the disposal works permit will be on-site at all times during construction.
12. a. All As-Built plans will be on site on the day of the final inspection.  
b. The As-Built plan will be considered as part of the Certificate of Compliance and will include ALL data as shown on proposed plan and ALL As-Built data.  
c. Original signatures and original engineer's stamps are required on all As-Built.  
d. The As-Built plan will also incorporate the following paragraph:

*The undersigned hereby declare that the sewage disposal system located at:*

---

Street	T own
has been installed in compliance with the provisions of 310 CMR 15.0 (Title V) and the design plans approved by the Halifax Board of Health relating to the application for the Disposal Works Construction Permit.	
Designer	Date
Installer	Date
Inspector	Date